

ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Dated 23rd December 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., of 24th January 1931, for Constructing a Primary School Building at Narasandra of Magadi Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tender should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3. (a) Tenders quoting percentages above or below estimate will be rejected.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for Constructing a Primary School Building at Narasandra Magadi Taluk, in default of which tenders will be rejected.

5. The final acceptance of tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board of the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted against each item of work both in words and figures.

Abstract estimate for constructing Primary School Building as per Revised No. II Type Design at Narasandra Magadi Taluk.

No.	Items of work.	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavation for foundation and filling in basement level and watering and tamping, etc., complete.	Cyds.		44	
2	Filling foundation with burnt stone jelly concrete in mortar.	C.ft.		260	
3	Do foundation and basement in burnt stone in clay, with bond stones as per specification.	"		1,333	
4	Superstructure burnt brick in clay with bond slabs as per specification.	"		1,196	
5	Do burnt brick in mortar	"		156	
6	Burnt stone slabs 6" thick roughly dressed and fixed	S.ft.		230	
7	Teakwood battened doors, 1 1/2" thick plank shutters, with iron fittings, of complete.	"		45 1/2	
8	Teakwood battened windows 1" thick plank shutter, put side only, with 3/4" iron bars and iron fittings, etc., complete.	"		63	
9	Teakwood gate small for air rooms	"		30	
10	Teakwood gate large for compound with double shutter and iron fittings complete.	"		20	
11	Teakwood work wrought and put up with wood oiling, etc., complete.	C.ft.		98.82	
12	Roofing with 1st Class Basel Mission Mangalore Tiles on 2" x 1" teak reepers do	Sqr.		18.84	
13	Ridge tiles set in mortar plain	R.ft.		164	
14	Plastering with mortar	Sqr.		42.00	
15	White and colour washing 2 coats	"		42.00	
16	Painting with mortar to basement	"		4.00	
17	Tarring to wood worn 2 coats	"		4.00	
18	Chocolate painting 3 coats	"		4.00	
19	Flooring with 1 1/2" thick Cuddapah slabs on 3" concrete bed and cement pointing, etc., complete.	"		19	
20	Coping over compound wall	R.ft.			